



November 24, 2004

Con 12-1-1 Doc # 32986

Ms. Nina Koger, Lead Engineer Energy & Waste Management Bureau Iowa Department of Natural Resources 502 East 9th Street Des Moines, Iowa 50319

RE:

2004 Annual Groundwater Quality Report

City of Muscatine C&D Landfill

70-SDP-4-78C P.N. 6008

Ms. Koger:

Find attached a copy of the 2004 Annual Groundwater Quality Report for the City of Muscatine C&D Landfill.

A copy of this data has been forwarded to Mr. Lavene Payne, Solid Waste Manager and Field Office #6 as required by the Permit.

Sincerely,

FOX ENGINEERING ASSOCIATES, INC.

Tago Wego

Todd Whipple, CPG Project Manager

Water | Wastewater | Solid Waste |

1601 Golden Aspen Dr.
Suite 103
Ames, Iowa 50010
1.515.233.0000
1.800.433.3469
Fax 1.515.233.0103
www.foxeng.com

info@foxeng.com

FOR THE

MUSCATINE C&D LANDFILL

by:
FOX Engineering, Inc.
1601 Golden Aspen Drive, Suite 103
Ames, Iowa 50010
(515) 233-0000



November 22, 2004

Ms. Nina Koger, Lead Engineer IDNR – Energy & Waste Management Bureau Wallace State Office Building 502 E. 9th Street Des Moines, Iowa 50319

RE: Muscatine C&D Landfill

CLOSURE PERMIT # 70-SDP-4-78C

FOX PN 6008-03B.320

Dear Ms. Koger:

This Annual Groundwater Quality Report has been prepared in accordance with IAC 567-113.26(8).

ANNUAL REPORT

- 1. **Effects on Surface Water:** Surface water at the site is controlled by vegetation and City street infrastructure. There are no surface water points being sampled at the present time.
- 2. Effects on Groundwater: A summary of analytical data for each monitoring well in the HMSP and the Analytical Reports for the past year are included as Attachment A. A summary of the statistical computations for the upgradient Water Table Well (MW-6) is included in the Concentration versus Time spreadsheets in Attachment B. The concentrations of the various compounds detected in each well are graphed over time versus the statistical limits calculated in the upgradient wells. The graphs are included in the spreadsheets in Attachment B.

The monitoring system includes monitoring wells intersecting the water table surface within glacial tills. The effects to the groundwater are discussed below.

Monitoring wells comprising the Hydrologic Monitoring System Plan (HMSP) include MW 6 (upgradient) and MW 2, 3, 4, and 7 (downgradient). Analytical results from upgradient monitoring well MW-6 indicate historically detected concentrations of chloride, COD, iron, nitrogen ammonia, phenol, and TOX. The presence of the compounds in the upgradient well suggest that the compounds are endemic to the region, or, conversely, that a upgradient source of the compounds exists.

Detected concentrations in all monitoring wells are below the Primary Drinking Water MCL. Each of the downgradient wells MW-2, MW-3, MW-4, and MW-7 exhibit compound concentrations in excess of the Secondary Drinking Water MCL for iron. Similarly, the

chloride concentration at MW-3 exceeded the Secondary Drinking Water MCL in January, 1996; April, 1998; and October, 1998.

Those compounds that exceed the calculated statistical limit, but not the MCL are summarized by well as follows:

MW-2 - COD (10/99), TOX (10/96), phenol (10/98 & 10/00).

MW-3 - iron, chloride, nitrogen ammonia (7/95), COD, TOX (10/96), phenol (10/98).

MW-4 - chloride, COD (4/99), TOX (10/96 & 10/98), phenols(10/98).

MW-7 - iron (10/98), COD (4/99), TOX (10/96), phenol (10/98)

Due to the presence of detectable concentrations of each of the listed compounds in the upgradient well, the elevated levels in the downgradient wells listed above are not interpreted as an indication of a leachate release into groundwater.

The detection of a compound above statistical limits during a single episode or during isolated episodes are not interpreted to represent a persistent leachate release. The interpretation is made that detection above the statistical limits during a single event, or during isolated episodes represents anomalous conditions in the well, the site conditions, or in the sampling activities.

Each parameter will continue to be routinely sampled and evaluated in accordance with the Special Provisions of the Permit.

3. Monitoring Well Maintenance and Performance Evaluation: Monitoring Well Performance Evaluation Reports dated April, 1999 and August, 2004 were prepared and submitted in accordance with IAC 567-113.21. The report concluded that the integrity of all MW's was intact, and that no changes in the HMSP were recommended. Monitoring well reevaluation is tentatively scheduled for the summer of 2009, and should again include all monitoring wells included in HMSP.

Review of the water elevation data for 2004 does not indicate excessive variability compared to historic water elevation data. Water elevation data is summarized in Attachment C. Based on the available water elevation data, the assessment of well conditions, and the hydrologic conditions at the site, the semi-annual water level measurements are interpreted to be sufficient to gauge notable changes in the site hydrology.


Flow paths are illustrated on the Groundwater Contour Map included in Attachment D.

4. Leachate Control Plan: This landfill is currently exempt from providing and implementing a leachate control system plan as per the Closure Permit. The conditional exemption is common in many Closure Permits at sites that were closed prior to installation of leachate collection systems. Our recent semi-annual Engineering's inspections have not revealed leachate seeps at the site.

5. **Explosive Gas Monitoring:** Explosive gas monitoring ceased at the site in 1998 based on authorization by IDNR in Provision 2, Permit Amendment #1, dated September 15, 1998 (Attachment E).

6. Recommendations:

- a. Continue routine monitoring of the HMSP monitoring wells and re-evaluate as part of the 2005 Annual Groundwater Quality Report due November 30, 2005.
- b. Continue water elevation measurements on a semi-annual basis.
- c. Continue Engineer's inspections on a semi-annual basis.
- d. Continue to monitor the integrity of the landfill cap.



ATTACHMENT A Analytical Results & Summary Tables

CITY OF MUSCATINE C&D LANDFILL 70-SDP-4-78C MONITORING WELL SAMPLING RESULTS

		SAMPLING	DATE:	03/03/04		
	D.G.W	D.G.W	D.G.W	U.G.W	U.G.W	
PARAMETER	MCL	MW 2	MW 3	MW 4	MW 6	MW 7
ug/L						
Benzene *	5	NT	NT	NT	NT	NT
Carbon tetrachloride *	5	NT	NT	NT	NT	NT
1,4-Dichlorobenzene *	0.6		NT	NT	NT	NT
1,2-Dichloroethane *		NT	NT	NT	NT	NT
1,1-Dichloroethylene *	7	NT	NT	NT	NT	NT
1,1,1-Trichloroethane *	200	NT	NT	NT	NT	NT
Vinyl Chloride	2	NT	NT	NT	NT	NT
cis-1,2-Dichloroethylene	70	NT	NT	NT	NT	NT
Tetrachloroethylene *	5	NT	NT	NT	NT	NT
Trichloroethylene *	5	NT	NT	NT	NT	NT
mg/L						
Arsenic, dissolved	0.05	NT	NT	NT	NT	NT
Barium, dissolved	2	NT	NT	NT	NT	NT
Cadmium, dissolved	0.005	NT	NT	NT	NT	NT
Chromium, dissolved	0.1		NT	NT	NT	NT
Copper, dissolved	1.3	NT	NT	NT	NT	NT
Zinc, dissolved	5	NT	NT	NT	NT	NT
Lead, dissolved	0.015	NT	NT	NT	NT	NT
Mercury, dissolved	0.002	NT	NT	NT	NT	NT
Magnisium, dissolved		NT	NT	NT	NT	NT
Iron, dissolved	0.3	0.466	3.38	0.108	<0.3	dry
Chloride	250	<10	85	61	84	dry
Nitrogen, Ammonia		<1.0	<1.0	<1.0	<1.0	dry
Chemical Oxygen Dema		<10	25	18	<10	dry
Phenols		NT	NT	NT	NT	NT
TOX		NT	NT	NT	NT	NT
рН	6.5-8.5	7.6	7.1	6.7		dry
Temperature, celsius		7	7	10		dry
Conductivity		624	1580	1210	921	dry







Accreditations: Iowa DNR: 095 New Jersey DEP: IA001 Kansas DHE: E-10287

ANALYTICAL REPORT

March 09, 2004

Page 1 of 2

Work Order: 14C0253

Report To

Todd Whipple

Fox Engineering Associates, Inc. 1601 Golden Aspen Drive, Suite 103

Ames, IA 50010

Project: Landfill

Project Number: Muscatine C & D

Work Order Information

Date Received: 03/04/2004 10:00AM Collector: Freeman, Richard

Phone: 515-233-0000

PO Number:

Analyte	Res	sult	MRL	Method		Analyzed Qualifier
4C0253-01 MW-6				Matrix: Water	· ·	Collected: 03/03/04 10:10
Determination of Conventional Chemi	stry Parame	ters				
Chemical Oxygen Demand	<10		10	EPA 410.4	SAA	03/09/04 8:25
Nitrogen, Ammonia	<1.0	mg/l	1.0	SM 4500-NH3 F	SAA	03/09/04 14:57
Chloride	84	mg/l	10	EPA 9252	SAA	03/08/04 17:07
Determination of Dissolved Metals						00/00/04 16 10
Iron, dissolved	<0.030	mg/l	0.030	EPA 6010B	LAR	03/08/04 16:19
14C0253-02 MW-2	٠٠.			Matrix: Water		Collected: 03/03/04 11:05
Determination of Conventional Chemi	stry Parame	ters				•
Nitrogen, Ammonia	<1.0		1.0	SM 4500-NH3 F	SAA	03/09/04 14:57
Chloride	<10	mg/l	10	EPA 9252	SAA	03/08/04 17:07
Chemical Oxygen Demand	<10	mg/l	. 10	EPA 410.4	SAA	03/09/04 8:25
Determination of Dissolved Metals		•				
Iron, dissolved	0.466	mg/l	0.030	EPA 6010B	LAR	03/08/04 16:19
14C0253-03 MW-3				Matrix: Water		Collected: 03/03/04 11:15
Determination of Conventional Chem	istry Parame	eters				
Chemical Oxygen Demand	25	mg/l	10	EPA 410.4	SAA	03/09/04 8:25
Nitrogen, Ammonia	<1.0	mg/l	1.0	SM 4500-NH3 F	SAA	03/09/04 14:57
Chloride	85	mg/l	10	EPA 9252	SAA	03/08/04 17:07
Determination of Dissolved Metals					1.45	00/00/04 16:10
Iron, dissolved	3.38	mg/l	0.030	EPA 6010B	LAR	03/08/04 16:19
14C0253-04 MW-4				Matrix:Water		Collected: 03/03/04 10:30
Determination of Conventional Chem	istry Param	eters				
Nitrogen, Ammonia	<1.0	mg/l	1.0	SM 4500-NH3 F	SAA	03/09/04 14:57
Chloride	61	mg/l	10	EPA 9252	SAA	03/08/04 17:07
Chemical Oxygen Demand	18	mg/l	10	EPA 410.4	SAA	03/09/04 8:25
Determination of Dissolved Metals				·		00/00/04 16 10
Iron, dissolved	0.108	mg/l	0.030	EPA 6010B	LAR	03/08/04 16:19

MRL= Method Reporting Limit.







Fox Engineering Associates, Inc. 1601 Golden Aspen Drive, Suite 103 Ames, IA 50010

Work Order: 14C0253

March 09, 2004

Page 2 of 2

14C0253-04

MW-4

Matrix: Water

Collected: 03/03/04 10:30

End of Report

Keystone Laboratories, Inc. Jeffrey King, Ph.D.

Laboratory Director

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety. Samples were preserved in accordance with 40 CFR for pH adjustment unless otherwise noted. MRL= Method Reporting Limit.



<u>Ω</u>
☐ 600 E. 17 th St. S. Newton, IA 50208 Phone: 641-792-8451 Fax: 641-792-7989
3012 Ansborough Ave. Waterloo, IA 50701 Phone: 319-235-4440 Fax: 319-235-2480 www.keystonelabs.com
1304 Adams Kansas City, KS 66103 Phone: 913-321-7856 Fax: 913-321-7937

Shir 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	CLIENT CLIENT TIME SAMPLE NUMBER DATE SAMPLE	SAMPLER: MICHARID GAMASSITE NAME: MICHARID GAMASSITE NAME: MICHARID GAMASSITE NAME: MICHARID GET	LABORATORIES, INC.
1 3 M/ X	NO. OF CONTAINERS MATRIX GRAB/COMPOSITE *** AN	REPORT TO: Tall Mingle NAME: Fax Engl ADDRESS: FAX: F5/5-390-669= FAX: FAX:	641-792-7989 Fax: 319-235-2480 www.keystonelabs.com
	ANALYSES REQUIRED LABORATORY WORK ORDER NO. 40 0253 SAMPLE TEMPERATURE UPON RECEIPT: °C NUMBER SAMPLE SAMPLE SAMPLE CONDITION/COMMENTS	BILL TO: MR LOW! NAME: MR LOW! COMPANY NAME: MACE ADDRESS: LOGG CITY/ST/ZIP: MUSATE CHONE: Keystone Quote No.:)

		Relinquished by: (Signature)	Know Euroman	Relinquished by: (Signature)				t MW	MW 3	mw 2	Hoffs grow	CLIENT E	
-	Time	Date	Time	Date				10311	IIISAT	110thm	MAS MOT	TIME	
Original - Return with Report		Received for Lab by: (Signature)		Received by: (Signature)				4 / 1	7) / 3		Monopoing bull le	SAMPLE LOCATION	
•	1 tel	7						1		2 (2	NO. OF CONTAINERS	
Yellow - Lab Copy	IDLODAN-	Date 1/84	Time	Date					^		7	MATRIX GRAB/COMPOSITE	
opy •	AM	*									X	" A	
Pink - Sampler Copy	111111148	Remarks: Mytals		Turn-Around: Standard								NALYSES REQUIRED	
FOI uni. OCI .	EODW. CCB 7.97	als Jamphs Line	Contact Lab Prior to Submission	Rush				04		02		LAB USE ONLY LABORATORY WORK ORDER NO. 440 0253 SAMPLE TEMPERATURE UPON RECEIPT: C SAMPLE SAMPLE SAMPLE SAMPLE NUMBER	

Site Name CITY of Musc	ATINE CED Lan	drill Permit No. 70)-SDP-4-78C
Monitoring Well/Piezometer No.	MW-2	Upgradient Downgradient	·
Name of person sampling	Richard Free		
A.) MONITORING WI	ELL/PIEZOMETER CON	IDITIONS	
Well/Piezometer Pi If no, exp <u>lain</u>	roperly Capped?		ing Water or Litter? No explain
B.) GROUNDWATER	ELEVATION MEASUR	EMENT (+/- 0.01 foot, N	ASL)
Elevation: Top of Depth of Well Equipment Used		・86 Ground Eler iside Casing Diameter (i	
Groun	dwater Level (+/- 0.01 fo	ot below top of inner ca	sing, MSL):
	Date/Time	Depth to Groundwater	Groundwater Elevation
Before Purging *After Purging *Before Sampling	3/3/04 11:05	719 28.0 8.4	
C.) WELL PURGING		·	
	r Removed from Well (gnes (based on current word/bailed dry?		
Equipment used Bailer type Pump type If not dedic	PVC	'Dedicated Ba 'Dedicated Ba Alconox & cla	
D.) FIELD MEASUR	EMENT		
Temperatur Equip pH Equip Specific Conditio	nts (after stabilization): e	Units OMPANY POCKET	PAL T PAL
• •		. •	ET LAL
	b		an locations of all surface and
NOTE: Attach La groundv	poratory Report and 8-1: vater monitoring points.	2" x 11" site plan snowir One map per sampling i	ng locations of all surface and round.
*Omit if only measuri	ng groundwater elevatio	ns.	

Site Name CITY of Musc	ATINE CED	Landfill Permit No	o. <u>170-</u>	SDP-4-78	3
Monitoring Well/Piezometer No.	MW-3	Upgradie			
Name of person sampling	Richard	Downgra Freeman	dient /	· · · · · · · · · · · · · · · · · · ·	
A.) MONITORING WE	LL/PIEZOMETER	RCONDITIONS			
Well/Piezometer Pro	operly Capped?_	<u> 405 </u>	Standing \ If yes, exp	Water or Litter?	No
B.) GROUNDWATER	ELEVATION ME	ASUPEMENT (+/- 0.	.01 foot, MSL)	
Elevation: Top of Depth of Well Equipment Used	inner well casing 22. Ole SOLINST	(4 <u>4</u> 0・3 () Gr Inside Casing D		on 638,30 ches) 2.0"	
Ground	twater Level (+/- (0.01 foot below top o	f inner casing	, MSL):	
	Date/Time	Depth to Groundw		Groundwater Elevation	٠
Before Purging *After Purging *Before Sampling	3 3 64	10·35 17·0 10·4			
C.) WELL PURGING					
Quantity of Water No.of Well Volum Was well pumper	es (based on cun	Vell (gallons) (grent water level) 3			
Equipment used: Bailer type Pump type If not dedic	PVC ated, method of c	'Dec	dicated Bailer dicated Bailer x & clean		
D.) FIELD MEASURE	EMENT				
Weather Condition	ts (after stabilizat	ion):			•
Temperature Equip	ment Used HA	Units CH COMPANY F	DCKET PA	14	
Specific Condition	ment Used HA	CH COMPANY Units CH COMPANY	POCKET	PAL PAL	
Comments					
NOTE: Attach La groundv	boratory Report a vater monitoring p	nd 8-12" x 11" site pl oints. One map per s	an showing losampling rour	ocations of all sur nd.	face and

*Omit if only measuring groundwater elevations.

Site Name CITY of MUSCATINE C.D Land	//// Permit No
Monitoring Well/Piezometer No. MW-4	Upgradient
Name of person sampling Richard Freen	1an
A.) MONITORING WELL/PIEZOMETER CONI	DITIONS
Well/Piezometer Properly Capped?	Standing Water or Litter? No If yes, explain
B.) GROUNDWATER ELEVATION MEASURE	MENT (+/- 0.01 foot, MSL)
Elevation: Top of inner well casing (eq3) Depth of Well 24.43 Ins Equipment Used SOLINGT	·22 Ground Elevation 691·29 side Casing Diameter (in inches) 2.0"
Groundwater Level (+/- 0.01 foo	ot below top of inner casing, MSL):
Date/Time	Depth to Groundwater Groundwater Elevation
Before Purging *After Purging *Before Sampling *Before Sampling	20:45 23:0 20:5
C.) WELL PURGING Quantity of Water Removed from Well (ga	ilions) I gal
No.of Well Volumes (based on current was Was well pumped/bailed dry?	ter level) VDI
Equipment used: Bailer type Pump type If not dedicated, method of cleaning	'Dedicated Bailer 'Dedicated Bailer Alconox & Clean water rinse
D.) FIELD MEASUREMENT	
Weather Conditions Cloudy 37° Field Measuments (after stabilization): Temperature 10 Equipment Used Hack Co	Units Units DMPAWY POCKET PAL
pH <u>(o`7</u> Equipment Used HACH	COMPANY FOCKET PAL
Specific Conditions 12.10	Units COMPANY POCKET PAL.
Comments	•
NOTE: Attach Laboratory Report and 8-12 groundwater monitoring points. C	"x 11" site plan showing locations of all surface and one map per sampling round.
*Omit if only measuring groundwater elevation	NS.

Site Name CITY of MUSCATINE CED Landful	Permit No. 70-50P-4-78C
Monitoring Well/Piezometer No. MW-6	Upgradient /
Name of person sampling Richard Freema	Downgradient (L)
A.) MONITORING WELL/PIEZOMETER CONDIT	TIONS
Well/Piezometer Properly Capped?	Standing Water or Litter?
If no, explain	If yes, explain
B.) GROUNDWATER ELEVATION MEASUREM	ENT (+/- 0.01 foot, MSL)
Elevation: Top of inner well casing 716.6	Ground Elevation 714.65
Depth of Well <u>48.98</u> Insid Equipment Used <u>SOLINST</u>	e Casing Diameter (in inches) 2.0"
Groundwater Level (+/- 0.01 foot b	pelow top of inner casing, MSL):
Date/Time	Depth to Groundwater Groundwater Elevation
Before Purging *After Purging *Before Sampling *Before Sampling	43'85 48.0 43.80
C.) WELL PURGING	
Quantity of Water Removed from Well (gallo No.of Well Volumes (based on current water Was well pumped/bailed dry?	ons) gal r level) vol
Equipment used: Bailer type PVC	'Dedicated Bailer
Pump type If not dedicated, method of cleaning	'Dedicated Bailer Alconox & clean water rinse
D.) FIELD MEASUREMENT	
Specific Conditions 92	Units
Comments	
NOTE: Attach Laboratory Report and 8-12": groundwater monitoring points. On	x 11" site plan showing locations of all surface and e map per sampling round.

Site Name CITY of Musc	ATINE CFD Land	/// Permit No	-SDP-4-78C
Monitoring Well/Piezometer No.	mw-7	Upgradient/ Downgradient	,
Name of person sampling	Richard Freem	an Downgradient	
A.) MONITORING WE	ELL/PIEZOMETER COND	ITIONS	
Well/Piezometer Pr	roperly Capped?	Standing If yes, e	g Water or Litter? No xplain
B.) GROUNDWATER	ELEVATION MEASURE	MENT (+/- 0.01 foot, MS	SL)
Elevation: Top of Depth of Well Equipment Used	22·2 5 Ins i	Ground Eleva de Casing Diameter (in	ation 714.40 inches) 2.0"
Ground	dwater Level (+/- 0.01 fool	below top of inner casi	ng, MSL):
	Date/Time	Depth to Groundwater	Groundwater Elevation
Before Purging *After Purging *Before Sampling	3/3/04	21.98	· · · · · · · · · · · · · · · · · · ·
C.) WELL PURGING			
Quantity of Wate No.of Well Volum Was well pumpe	r Removed from Well (gal nes (based on current wat d/bailed dry?		SAMPLE
Equipment used: Bailer type Pump type If not dedic	PVC	'Dedicated Bail 'Dedicated Bail Alconox & clequ	er
D.) FIELD MEASURI	EMENT		
Temperature	nts (after stabilization): e	Units Units	Pal
pH			
Specific Condition	ons	Units OMPANY POCKET	T PAL
Comments			
NOTE: Attach La		x 11" site plan showing	plocations of all surface and und.
*Omit if only measuri	ng groundwater elevations	S.	

CITY OF MUSCATINE C&D LANDFILL 70-SDP-4-78C MONITORING WELL SAMPLING RESULTS

		SAMPLING	DATE:	09/08/04		
			D.G.W	D.G.W	U.G.W	U.G.W
PARAMETER	MCL	MW 2	MW 3	MW 4	MW 6	MW 7
ug/L						
Benzene *						NT
Carbon tetrachloride *	5	NT	NT	NT	NT	NT
1,4-Dichlorobenzene *	0.6	NT	NT	NT	NT	NT
1,2-Dichloroethane *	5	NT	NT	NT	NT	NT
1,1-Dichloroethylene *	7	NT	NT	NT	NT	NT
1,1,1-Trichloroethane *	200	NT	NT	NT	NT	NT
Vinyl Chloride	2	NT	NT	NT	NT	NT
cis-1,2-Dichloroethylene	70	NT	NT	NT	NT	NT
Tetrachloroethylene *	5	NT	NT	NT	NT	NT
Trichloroethylene *	5	NT	NT	NT	NT	NT
mg/L						
Arsenic, dissolved			NT		NT	NT
Barium, dissolved		NT	NT	NT	NT	NT
Cadmium, dissolved	0.005	NT	NT	NT	NT	NT
Chromium, dissolved			NT	NT	NT	NT
Copper, dissolved		NT	NT	NT	NT	NT
Zinc, dissolved		NT	NT	NT	NT	NT
Lead, dissolved	0.015		NT ·	NT	NT	NT
Mercury, dissolved	0.002		NT	NT	NT	NT
Magnisium, dissolved		NT	NT	NT	NT	NT
Iron, dissolved	0.3	0.044	0.082	<0.030	<0.030	dry
Chloride	250	<10	92	28		dry
Nitrogen, Ammonia		<1.0	1.2	<1.0	<1.0	dry
Chemical Oxygen Dema		11	24	12	<10	dry
Phenols		<.100	<0.100	<0.100	<0.100	NT
TOX		<0.010	0.032	0.021	0.018	NT
		·	1	1	1	
рН	6.5-8.5	7.6	7.1	6.7	7.2	
Temperature, celsius		18	17	16		dry
Conductivity		635	1524	940	898	dry







Accreditations: Iowa DNR: 095 New Jersey DEP: IA001 Kansas DHE: E-10287

ANALYTICAL REPORT

September 17, 2004

Page 1 of 2

Work Order: 14I0228

Report To

Todd Whipple

Fox Engineering Associates, Inc.

1601 Golden Aspen Drive, Suite 103

Ames, IA 50010

Project: Muscatine C & D

Project Number: [none]

Work Order Information

Date Received: 09/07/2004 10:50AM

Collector: Richard Freeman Phone: 515-233-0000

PO Number:

Analyte	Res	ult	MRL	Method		Analyzed Qualifier
410228-01 MW 3				Matrix:Water	•	Collected: 09/05/04 07:50
Determination of Conventional Chemi	istry Paramet	ers				
Chemical Oxygen Demand	24 1		10	EPA 410.4	MAQ	09/13/04 12:33
Chloride	92 1		10	EPA 9252	SNT	09/08/04 13:22
Nitrogen, Ammonia	1.2		1.0	SM 4500-NH3 F	SAA	09/08/04 14:14
Phenols, total	< 0.100	_	0.100	EPA 9065	KRV	09/14/04 11:07
Total Organic Halogens (TOX)	0.032	mg/l	0.010	EPA 9020	TVK	09/14/04 0:00
Determination of Dissolved Metals Iron, dissolved	0.082	mg/l	0.030	EPA 6010B	LAR	09/13/04 15:58
14I0228-02 MW 2				Matrix: Water		Collected: 09/05/04 07:40
Determination of Conventional Chem	istry Parame	ters		·	G 4 4	00/12/04 0.51
Chemical Oxygen Demand		mg/l	10	EPA 410.4	SAA	09/13/04 9:51 09/08/04 13:22
Chloride	<10	_	10	EPA 9252	SNT	
Nitrogen, Ammonia	<1.0	_	1.0	SM 4500-NH3 F	SAA	09/10/04 15:41
Phenols, total	<0.100	mg/l	0.100	EPA 9065	KRV	09/14/04 11:07
Total Organic Halogens (TOX)	< 0.010	mg/l	0.010	EPA 9020	TVK	09/14/04 0:00
Determination of Dissolved Metals				•		
Iron, dissolved	0.044	mg/l	0.030	EPA 6010B	LAR	09/13/04 16:06
14I0228-03 MW 4				Matrix: Water		Collected: 09/05/04 08:20
Determination of Conventional Chem	istry Parame	eters				
Chemical Oxygen Demand	12	mg/l	10	EPA 410.4	SAA	09/13/04 9:51
Chloride	28	mg/l	10	EPA 9252	SNT	09/08/04 13:22
Nitrogen, Ammonia	<1.0	mg/l	1.0	SM 4500-NH3 F	SAA	09/10/04 15:41
Phenols, total	< 0.100	mg/l	0.100	EPA 9065	KRV	09/14/04 11:07
Total Organic Halogens (TOX)	0.021	mg/l	0.010	EPA 9020	TVK	09/16/04 15:25
Determination of Dissolved Metals						00/10/04 16 10
Iron, dissolved	< 0.030	mg/l	0.030	EPA 6010B	LAR	09/13/04 16:19
14I0228-04 MW 6				Matrix:Water		Collected: 09/05/04 08:40
THIUMMUTUT LITTI				2 -		

The results in this report apply to the samples analyzed in accordance with the chain of custody document. This analytical report must be reproduced in its entirety. Samples were preserved in accordance with 40 CFR for pH adjustment unless otherwise noted MRL= Method Reporting Limit.







Fox Engineering Associates, Inc. 1601 Golden Aspen Drive, Suite 103 Ames, IA 50010

Work Order: 14I0228

September 17, 2004

Page 2 of 2

Result	MRL	Method	Analyst	Analyzed	Qualifier
		Matrix:Water	(Collected: 09/	05/04 08:40
istry Parameters					
'<10 mg/l	10	EPA 410.4	SAA	09/13/04 9:	51
80 mg/l	10	EPA 9252	SNT	09/08/04 13	:22
<1.:0 mg/l	1.0	SM 4500-NH3 F	SAA	09/10/04 15	:41
<0.100 mg/l	0.100	EPA 9065	KRV	09/14/04 11	:07
0.018 mg/l	0.010	EPA 9020	TVK	09/16/04 15	:25
<0.030 mg/l	0.030	EPA 6010B	LAR	09/13/04 16	:23
	istry Parameters <10 mg/l 80 mg/l <1.0 mg/l <0.100 mg/l	istry Parameters <10 mg/l 80 mg/l 10 <1.0 mg/l 1.0 <0.100 mg/l 0.018 mg/l 0.010	Matrix:Water istry Parameters <10 mg/l 80 mg/l 10 EPA 410.4 EPA 9252 <1.0 mg/l 1.0 SM 4500-NH3 F <0.100 mg/l 0.100 EPA 9065 0.018 mg/l 0.010 EPA 9020	Matrix:Water Colored	Matrix:Water Collected: 09/ istry Parameters <10 mg/l 10 EPA 410.4 SAA 09/13/04 9: 80 mg/l 10 EPA 9252 SNT 09/08/04 13 <1.0 mg/l 1.0 SM 4500-NH3 F SAA 09/10/04 15 <0.100 mg/l 0.100 EPA 9065 KRV 09/14/04 11 0.018 mg/l 0.010 EPA 9020 TVK 09/16/04 15 Collected: 09/

End of Report

Jeffey King

Keystone Laboratories, Inc.

Jeffrey King, Ph.D. Laboratory Director

LABORATORIES, INC. ystone

000 E. 17th St. S. Newton, IA 50208 Phone: 641-792-8451 Fax: 641-792-7989

3012 Ansborough Ave. Waterloo, IA 50701 Phone: 319-235-4440 Fax: 319-235-2480

> ☐ 1304 Adams Kansas City, KS 66103 Phone: 913-321-7856

Fax:

913-321-7937

PAGE <u>유</u>

FAX:	PHONE:
PHONE / M/ 515-290-	CITY/ST/ZIP:
CITYST/ZIP: Am of	ADDRESS:
COMPANY NAME: FBX (3)	SITE NAME, MUSINATING CED
NAME: 1000 Whip	SAMPLER: TICHOR BELOW FIRPARAL
BEBORT TO:	DDINIT OD TYPE INCORPATION BEI OW

66 95 PHONE:	CITYISTIZIP: MINSCATUM, IT 5 X 14	ADDRESS: 1070 HOUS 113	COMPANY NAME: E. /sarx HI State	OP NAME: MUSCAMO KICGELLI	BILL TO: POR LOVEDS PROGOS ON BY	
	1017	11/1/	apya	60112	18/16	,

FOLUSI. OCT A ST	Pink - Sampler Copy	•	Vellow - I ah Conv	•	al Deturn with Benort	Original			-
EOBM: CCB 7-07	417110	Time /D; 50 A M	7 Time /D; S	Sill			Time		
Jamples 17410	Remarks: mp tals	Date 9/7/6 /	Date 9/7	nature)	Received for Lab by: (Signature)	Recei	Date	ure)	Relinquished by: (Signature)
Contact Lab Prior to Submission			Time	i		3,	Time	1	Ken been
	Turn-Around: Standard Rush	11	Date		Received by: (Signature)	100	20/20	ure)	Relinguished/by: (Signature)
					;				
(14)		111	_	5	/	ق 	840197		mule
						_		_	
6				7		3	820 PM		mw 4
					/				
のえ				7		3	745Am		MW 2
<i>J</i>			Í						
<i>C)</i>		ベスノ	Ż	56/	Monoterny heli		Mast.	h95K	E MU
LABORATORY WORK ORDER NO. C T 0 225 SAMPLE TEMPERATURE UPON RECEIPT: C LABORATORY SAMPLE NUMBER SAMPLE CONDITION/COMMENTS	LABORAT SAMPLE UPON RE SAMPLE	GRAB/COMPOSITE	MATRIX	NO. OF CONTAINERS	SAMPLE LOCATION	SAMPL	TIME	DATE	CLIENT SAMPLE NUMBER
TAP HER ONLY	יסבס סבטו ווסבט	ANIAN		1					

14/20

Original - Return with Report • Yellow - Lab Copy • Pink - Sampler Copy

Site Name CITY of Musc	ATINE CED	Landfill	Permit No.	·70-5	DP-4-78	3
Monitoring Well/Piezometer No.	_MW-Z		_Upgradient _	-4	,	
Name of passon compling	Richard	Freema	Downgradier	11 /	· · · · · · · · · · · · · · · · · · ·	
Name of person sampling	BICHAIL	1 1 ECHA	Kı			
A.) MONITORING WE	ELL/PIEZOMETE	R CONDIT				_
Well/Piezometer Pr If no, ex <u>plain</u>	operly Capped?	<u>405</u>		Standing W If yes, expla	ater or Litter?	ν ₀ =
B.) GROUNDWATER	ELEVATION ME	EASUREM	ENT (+/- 0.01 1	foot, MSL)		
Elevation: Top of	inner well casing	640.8	ھ Groun	d Elevation	638,70	·
Depth of Well	42.16		Casing Diam	eter (in inc	hes) 2.0"	
Equipment Used	SOLINST					
Ground	dwater Level (+/-	0.01 foot b	elow top of inr	ner casing,	MSL):	
	Date/Time		Depth to Groundwater	r	Groundwater Elevation	
Defere Durging	9/4/04		Q.Z			
Before Purging *After Purging	41101		25.0			
*Before Sampling	9/5/04 7	40am	8.2			
C.) WELL PURGING	· []	•				
Quantity of Water	Removed from	Well (gallor	ns) 9½			
No.of Well Volum	es (based on cu	rrent water	level) Z			
Was well pumped		No_				
	•					
Equipment used: Bailer type	PVC		'Dedicat	ted Bailer		
Pump type		·····	'Dedicat	ted Bailer		
If not dedicate	ated, method of o	deaning	Alconox	e clean v	vater rinse	
D.) FIELD MEASURE	EMENT		*			
Weather Conditio	ns cloudy	850				
Field Measumen	ts (after stabiliza	tion):				
Temperature	3 18·0		Units			
Equip	ment Used HA	KH COM	PANY POC	KET PAL		
pH	7.6		,			
Equip		ACH CO		CKET T	<u>ac</u>	
Specific Condition		ACH (c	_Units		P	
Equip	ment osed Pla	البادة رح	DWBANY 1	OCKET	_LA; L	
Comments						
NOTE: Attach Lal groundw	poratory Report a vater monitoring p	and 8-12" x points. One	11" site plan s map per sam	showing loo pling round	ations of all surf	face and

*Omit if only measuring groundwater elevations.

Site Name CITY of Musc	ATINE CED	Landfill Permit	No. 70)-SDP-4-78	<u></u>
Monitoring Well/Piezometer No.	MW-3	Upgrad	dient		
Manager of sever compling	Richard 1	Downg <u>reeman</u>	gradient	<u> </u>	
Name of person sampling	131cHara 1	recondu			
A.) MONITORING WE	ELL/PIEZOMETER	CONDITIONS			
Well/Piezometer Pr If no, explain	operly Capped?_	405		ing Water or Litter?	<u> </u>
B.) GROUNDWATER	ELEVATION MEA	ASUPEMENT (+/-	- 0.01 foot, I	MSL)	
Elevation: Top of	inner well casing	640.36	Ground Ele	vation 638,30	
Depth of Well	22.06	Inside Casing	g Diameter (in inches) 2.0"	
Equipment Used	SOLINST				
Ground	dwater Level (+/- 0	.01 foot below top	of inner ca	using, MSL):	
	Date/Time	Depth Groun	to dwater	Groundwater Elevation	٠
Before Purging *After Purging *Before Sampling	9/4/04	11-0 20-1 11-0	<u>0</u>		
C.) WELL PURGING	. , ,				
Quantity of Wate No.of Well Volun Was well pumpe	r Removed from V nes (based on curr d/bailed dry?	TON (ganono)	le 3		
Equipment used Bailer type Pump type If not dedic	PVC	"	Dedicated Background		
D.) FIELD MEASUR	EMENT		•		
Weather Condition Field Measurmer Temperatur	nts (after stabilizati	9.80° on): Units			
Equip pH Equip	ment Used HA 71 ment Used HA	CH COMPANY	POCKET Y POCKE	FAL T PAL	
Specific Condition	ons [524 oment Used HA	Units	my Poc	KET PAL	
Comments					
NOTE: Attach La ground	boratory Report arwater monitoring po	nd 8-12" x 11" site pints. One map pe	e plan showi er sampling	ing locations of all surf round.	face and

*Omit if only measuring groundwater elevations.

Site Name CITY of Musc	ATINE C.D La	<i>ndrill</i> Permit No	70-SDF	2-4-78 <u></u>	
Monitoring Well/Piezometer No.	MW-4	Upgradient _	•		
Name of person sampling	Bichard Fre	Downgradie <u>r</u> <u>eman</u>	ıt 🗸		
A.) MONITORING WE	ELL/PIEZOMETER CC	ONDITIONS			
Well/Piezometer Pr If no, ex <u>plain</u>	roperly Capped?		Standing Water f yes, expla <u>in</u>	or Litter? N	b
B.) GROUNDWATER	ELEVATION MEASU	REMENT (+/- 0.01 f	foot, MSL)		
Elevation: Top of Depth of Well Equipment Used	inner well casing (e ^c 24·43 SOUMST	73·22 Groun Inside Casing Diam	d Elevation (eter (in inches)		
Ground	dwater Level (+/- 0.01	foot below top of inn	ner casing, MS	L) :	
	Date/Time	Depth to Groundwater		oundwater vation	
Before Purging *After Purging *Before Sampling	9/4/04 8:20	20.6 20.6			
C.) WELL PURGING					
Quantity of Wate No.of Well Volum Was well pumpe	r Removed from Well (nes (based on current of d/bailed dry?	(gallons) Z water level) Z			
Equipment used: Bailer type Pump type If not dedic	PVC	'Dedicat	ed Bailer ed Bailer <i>clean had</i>	er rinse	
D.) FIELD MEASURI	EMENT				
Temperatum Equip pH	nts (after stabilization): e	Units Company Pocy	KET PAL		
Specific Condition	ment Used HACH ons 940	Units		·	
	ment Used HACH	COMPANY 1	SCKET I	£4	
NOTE: Attach La	boratory Report and 8- vater monitoring points	-12" x 11" site plan s	showing location	ns of all surface	e and
*Omit if only measuri	ng groundwater elevat	ions.			

Site Name CITY of Musc	ATINE CED Lan	dh// Permit No	0-SDP-4-78C
Monitoring Well/Piezometer No.	MW-6	Upgradient	/
Name of person sampling	Richard Free	Downgradient Man	
A.) MONITORING WI	ELL/PIEZOMETER CO	NDITIONS	
Well/Piezometer Pr If no, ex <u>plain</u>	roperly Capped?		ling Water or Litter? No explain
B.) GROUNDWATER	RELEVATION MEASUR	REMENT (+/- 0.01 foot, I	MSL)
Elevation: Top of Depth of Well Equipment Used		e· 63 Ground Elenside Casing Diameter (vation_7/4·65 (in inches)_2.0**
Groun	dwater Level (+/- 0.01 f	oot below top of inner ca	asing, MSL):
	Date/Time	Depth to Groundwater	Groundwater Elevation
Before Purging *After Purging *Before Sampling	9/4/04 9/5/04 8:40	43-7 49.0 44.9	
C.) WELL PURGING	,		
Quantity of Wate No.of Well Volun Was well pumpe	er Removed from Well (gines (based on current wild/bailed dry?	vater level) 1.5	
Equipment used Bailer type Pump type If not dedic	PVC	'Dedicated Ba 'Dedicated Ba 'Dedicated Ba	
D.) FIELD MEASUR		.0	
Temperatur Equip pH Equip Specific Conditi	nts (after stabilization): re /// pment Used HACH TO TO THE PROPERTY OF THE PR	Units Company Pocket Company Pocke Units Company Pocke	PAL T PAL KET PAL
Comments			
NOTE: Attach La ground	aboratory Report and 8- water monitoring points	12" x 11" site plan showi One map per sampling	ng locations of all surface and round.

*Omit if only measuring groundwater elevations.


Site Name CITY of Musc	ATINE CED LA	endfill Permit No. 70)-SDP-4-78_C
Monitoring Well/Piezometer No.	MW-7	Upgradient Downgradient	<u>/</u>
Name of person sampling	Richard Fre	Peman	
A.) MONITORING WE	ELLIPIEZOMETER CO	ONDITIONS	
Well/Piezometer Pro If no, explain	operly Capped?		ng Water or Litter? No explain ———
B.) GROUNDWATER	ELEVATION MEASL	JREMENT (+/- 0.01 foot, N	ISL)
Elevation: Top of Depth of Well Equipment Used	inner well casing 71 22:25 SOLINST	Ground Elev Inside Casing Diameter (i	vation 7/4·40 in inches) 2.0"
Ground	twater Level (+/- 0.01	foot below top of inner cas	sing, MSL):
	Date/Time	Depth to Groundwater	Groundwater Elevation
Before Purging *After Purging *Before Sampling	9/4/64	21.85	
C.) WELL PURGING Quantity of Water No.of Well Volum Was well pumper	Removed from Well es (based on current balled dry?	(gallons) 100 dv y water level)	to sample
Equipment used: Bailer type Pump type		'Dedicated Ba 'Dedicated Ba ing <u>Alconox & clea</u>	
D.) FIELD MEASURE	MENT		
Temperature Equipr pH Equipr Specific Conditio	ts (after stabilization): nent Used HACH	Units COMPANY POCKET	FAL T PAL
Comments			
NOTE: Attach Lab groundw	ooratory Report and 8 rater monitoring points	-12" x 11" site plan showin s. One map per sampling r	ng locations of all surface and ound.
*Omit if only measuring	ng groundwater eleva	tions.	

ATTACHMENT B Concentration versus Time Graphs

				U.W.T.	D.W.T.	D.W.T.	D.W.T.	D.W.T.
	PARAMETER	MCL	Mean + 2STD	MW 6	MW 2	MW 3	MW 4	MW 7
		mg/L						
04/15/95	Iron, dissolved	0.3	4.884		0.25			0.11
07/15/95	Iron, dissolved	0.3	4.884	0.02	0.18	7.94	0.05	0.01
10/15/95	Iron, dissolved	0.3	4.884	0.21	0.54	7.31	0.25	0.29
01/15/96	Iron, dissolved	0.3	4.884	0.74	0.59	6.41	0.06	0.81
04/15/96	Iron, dissolved	0.3	4.884	0.33	0.12	10.05	0.3	0.76
10/15/96	Iron, dissolved	0.3	4.884	0.07	1.16	6.33	0.09	0.31
04/15/97	Iron, dissolved	0.3	4.884	0.04	0.69	19.32	0.12	0.15
10/15/97	Iron, dissolved	0.3	4.884	0.015	0.54	15.1	0.015	dry
04/15/98	Iron, dissolved	0.3	4.884	0.1	0.6	21	0.1	0.1
10/15/98	Iron, dissolved	0.3	4.884	10.8	0.661	13.5	0.914	14.9
04/15/99	Iron, dissolved	0.3	4.884	0.0022	0.046	1.19	0.0022	0.0022
10/15/99	Iron, dissolved	0.3	4.884	0.413	0.0022	0.412	0.0022	0.0022
04/15/2000	Iron, dissolved	0.3	4.884	0.0022	0.583	11.7	0.0022	0.0022
10/15/2000	Iron, dissolved	0.3	4.884	0.008	0.653	7.4	0.014	0.0022
04/15/2001	Iron, dissolved	0.3	4.884	0.19	3.5	9.9	0.16	0.11
10/15/2001	Iron, dissolved	0.3	4.884	0.05	0.95	8.4	0.05	0.05
04/15/2002	Iron, dissolved	0.3	4.884	0.06	0.6	0.06	0.06	0.06
10/15/2002	Iron, dissolved	0.3	4.884	0.27	1	5.3	0.16	dry
03/13/2003	Iron, dissolved	0.3	4.884	<0.3	0.511	4.78	0.215	dry
09/04/2003	Iron, dissolved	0.3	4.884	<0.3	0.305	1.06	< 0.3	dry
03/03/2004	Iron, dissolved	0.3	4.884	< 0.30	0.466	3.38	0.018	dry
	Iron, dissolved	0.3	4.884	<0.3	0.305	1.06	< 0.3	dry

 Standard Deviation (STD)
 2.441971
 0.686609
 5.745508
 0.199601
 3.570497

 Mean + 2STD
 4.883942
 1.373218
 11.49102
 0.399203
 7.140994




GROUNDWATER SYSTEM
MUSCATINE C & D LANDFILL
70-SDP-4-78C
CONCENTRATION VERSUS TIME

				U.W.T.	D.W.T.	D.W.T.	D.W.T.	D.W.T.
	PARAMETER	MCL	Mean + 2STD	MW 6	MW 2	MW 3	MW 4	MW 7
		mg/L						
04/15/95		25			1.8			2.4
07/15/95	Chloride	25			1.8			6.5
10/15/95	Chloride	25	0 40.005		1.7	177.5		6.6
01/15/96	Chloride	25	0 40.005		2.3			6.8
04/15/96	Chloride	25	0 40.005	62.5	2.3	190	108.2	7.2
10/15/96	Chloride	25	0 40.005	49.6	2.5	169.8	62.3	6.4
04/15/97	Chloride	25	0 40.005	58.9	0.5	160.4	112.3	10.3
10/15/97	Chloride	25	0 40.005	72	8	200	69	dry
04/15/98	Chloride	25	0 40.005	120	13	450	150	28
10/15/98	Chloride	25	0 40.005	60.1	21.8	273	54.6	21.8
04/15/99	Chloride	25	0 40.005	69.2	0.5	54.3	90.5	12.4
10/15/99	Chloride	25	0 40.005	64.7	10.5	195	91.1	6.2
04/15/2000	Chloride	25	0 40.005	55.8	0.5	204	103	12.4
10/15/2000	Chloride	25	0 40.005	39	0.5	133	67.4	3.37
04/15/2001	Chloride	25	0 40.005	46.8	2.5	196	118	6.8
10/15/2001	Chloride	25	0 40.005	66.3	2.5	164	53.1	7
04/15/2002	Chloride	25	0 40.005	48	0.5	139	51	5
10/15/2002	Chloride	25	0 40.005	64	1.4	110	46	dry
03/13/2003	Chloride	25	0 40.005	90	<10	116	50	dry
/ 09/04/2003	Chloride	25	0 40.005	86	<10	108	42	dry
03/03/2004	Chloride	25	0 40.005	84	<10	85	61	dry
≯ _{09/04/2003}	Chloride	25		86	<10	108	42	dry

 Standard Deviation (STD)
 20.00268
 5.533858
 83.10865
 30.85907
 6.53245


 Mean + 2STD
 40.00536
 11.06772
 166.2173
 61.71815
 13.0649



				U.W.T		D.W.T.	D.W.T.	D.W.T.	D.W.T.
PAI	RAMETER	MCL	Mean + 2STE	MW 6		MW 2	MW 3	MW 4	MW 7
	r	ng/L							
	rogen, Ammonia		3.003	3	0.86	1.56			
07/15/95 Nitr	rogen, Ammonia		3.003	3	6.7	2.19		7 1.91	1.42
10/15/95 Nitr	rogen, Ammonia		3.003		0.47	1.38			2.94
01/15/96 Nitr	rogen, Ammonia		3.003	3	0.56	1.62	1.56	6 0.51	0.78
04/15/96 Nitr	rogen, Ammonia		3.003		0.1	1.25			80.0
10/15/96 Nitr	rogen, Ammonia		3.003	3	0.06	1.17	1.3	0.025	0.06
04/15/97 Nitr	rogen, Ammonia		3.003	3	0.06	1.22			
10/15/97 Nitr	rogen, Ammonia		3.003	3	0.09	1.17			dry
04/15/98 Nitr	rogen, Ammonia		3.003		0.05	2.4	2.8	3 0.05	
10/15/98 Nitr	rogen, Ammonia		3.003		.025	1.29		0.108	
04/15/99 Nitr	rogen, Ammonia		3.003		0.25	1.2			
10/15/99 Nitr	rogen, Ammonia		3.003		0.65	2.2			
	rogen, Ammonia		3.003		.448	0.336	0.448	0.025	0.025
	rogen, Ammonia		3.003	3 0	.025	0.4	0.0	0.025	1
	rogen, Ammonia		3.003	3	0.1	1	1.02	2 0.1	0.1
	rogen, Ammonia		3.003	3	0.1	1.2	1.48	3 0.1	0.1
	rogen, Ammonia		3.003		0.11	0.46			0.254
	rogen, Ammonia		3.003	3 0	.025	1.2	1.4	0.13	dry
	rogen, Ammonia		3.003	3 <1		1.1	1.1	l <1	dry
09/04/2003 Nitr	rogen, Ammonia		3.003	3 <1	1	1.4	1.3	2 <1	dry
	rogen, Ammonia		3.003	3 <1.	.0	<1.0	<1.0	<1.0	dry
09/08/2004 Nitr	rogen, Ammonia		3.003	3 <1.	.0	<1.0	1.3	2 <1.0	dry

 Standard Deviation (STD)
 1.501318
 0.531177
 1.238449
 0.436515
 0.741713


 Mean + 2STD
 3.002637
 1.062353
 2.476898
 0.873029
 1.483426




	PARAMETER	MCL mg/L	Mean + 2STD	U.W.T. MW 6	D.W.T. MW 2	D.W.T. MW 3	D.W.T. MW 4	D.W.T. MW 7
04/15/95	COD		156.864	2.9	0.05	42	74	4.3
07/15/95			156.864	62	42	31	63	2.8
10/15/95			156.864	63	42	42	31	5.1
01/15/96	COD		156.864	165	31	130	63	63
04/15/96	COD		156.864	188	74	188	74	53
10/15/96	COD		156.864	31	21	290	63	21
04/15/97	COD		156.864	31	10	97	42	42
10/15/97	COD		156.864	2.5	2.5	82	31	dry
04/15/98	COD		156.864	2.5	2.5	31	25	8
10/15/98	COD		156.864	2	16	47	25	2
04/15/99	COD		156.864	10	10	31	29	10
10/15/99			156.864	293	585	191	252	170
04/15/2000	COD		156.864	84.1	53.1	162	120	44.3
10/15/2000	COD		156.864	57.5	53.1	164	44.3	90.7
04/15/2001	COD		156.864	2.5	2.5	32	14	2.5
10/15/2001			156.864	2.5	2.5	30	14	2.5
04/15/2002	COD		156.864	23.8	NT	107	25.9	43.4
10/15/2002			156.864	3	3	20		dry
03/13/2003	COD		156.864	<10	<10	20		dry
09/04/2003	COD		156.864	<10	<10	28		dry
03/03/2004			156.864	<10	<10	25		dry
09/08/2004	COD		156.864	<10	11	24	12	dry

Standard Deviation (STD) 78.4321 130.7134 73.02038 52.06372 43.49214


Mean + 2STD 156.8642 261.4268 146.0408 104.1274 86.98428



	PARAMETER	MCL	Mean + 2STD	U.W.T. MW 6	D.W.T. MW 2	D.W.T. MW 3	D.W.T. MW 4	D.W.T. MW 7
40/45/05		mg/L	0.062	0.05	0.05	0.05	0.05	0.05
10/15/95							0.03	0.03
10/15/96			0.062		0.1	0.1		
10/15/97	· - · ·		0.062		0.0025	0.026	0.007	0.0001
10/15/98	TOX		0.062	0.011	0.0025	0.019	0.945	0.01
10/15/99	TOX		0.062	0.001	0.001	0.001	0.001	0.001
10/15/2000	TOX		0.062	0.05	0.05	0.05	0.05	0.05
10/15/2001	TOX		0.062	0.005	0.005	0.018	0.024	0.005
10/15/2002	TOX		0.062	0.011	0.0025	0.029	0.031	dry
09/04/2003	TOX		0.062	<0.01	<0.01	0.018	0.014	dry
09/08/2004	TOX		0.062	0.018	<0.010	0.032	0.021	dry
	Standard Deviation (STD))		0.030784	0.034181	0.02605	0.274908	0.034754
	Mean + 2STD			0.061568	0.068363	0.0521	0.549816	0.069507



	DADANETED	1401	Maria A COTO	U.W.T.	D.W.T.	D.W.T.	D.W.T.	D.W.T.
	PARAMETER	MCL mg/L	Mean + 2STD	MVV 6	MW 2	MW 3	MW 4	MW 7
10/15/95	Phenols		0.024	0.005	0.005	0.005	0.005	0.005
10/15/96	Phenois		0.024	0.01	0.01	0.01	0.01	0.01
10/15/97	Phenols		0.024	0.016	0.018	0.018	0.016	dry
10/15/98	Phenois		0.024	0.025	0.025	0.025	0.025	0.025
10/15/99	PhenoIs		0.024	0.0025	0.0025	0.0025	0.0025	0.0025
10/15/2000	PhenoIs		0.024	0.0025	0.0318	0.0025	0.0025	0.0025
10/15/2001	PhenoIs		0.024	0.01	0.01	0.01	0.01	0.01
10/15/2002			0.024		0.0025	0.0025	0.0025	dry
09/04/2003			0.024		<0.1	<0.1	<0.1	dry
09/08/2004	PhenoIs		0.024	<0.100	<0.100	<0.100	<0.100	dry
	Mean			0.009188	0.0131	0.009438	0.009188	0.009167
	Standard Deviation (ST	D)		0.007496	0.010154	0.007748	0.007496	0.007728
	Mean + 2STD			0.024179	0.033408	0.024933	0.024179	0.024623




ATTACHMENT C Water Elevation Data

Water Level Data Muscatine C&D Landfill

Well/TOC	MW-1	640.42	MW-2	640.86	MW-3	640.36	MW-4	693.22	MW-5	716.8	MW-6	716.63	MW-7	716.65	PZ-8	692.99
Depth of Well		67.09		42.6		22.06		24.43		76.5		48.98		22.25		46
													ı			
	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water	Water
Date	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation	Depth	Elevation
11/04/93	NT	NT	6.24	634.62	7.08	633.28	16.44	676.78	70.75	646.05	39.38	677.25	16.35	700.3	42.05	650.94
11/23/93	5.60	634.82	6.05	634.81	7.24	633.12	16.94	676.28	57.04	659.76	48.94	667.69	16.72	699.93	42.30	650.69
12/09/93	5.64	634.78	6.10	634.76	7.53	632.83	17.20	676.02	53.54	663.26	40.76	675.87	17.15	699.5	NT	NT
12/16/93	6.22	634.2	7.71	633.15	7.62	632.74	17.49	675.73	52.57	664.23	41.05	675.58	17.70	698.95	NT	NT
01/20/94	5.97	634.45	6.40	634.46	8.46	631.9	18.05	675.17	50.95	665.85	52.57	664.06	18.50	698.15	42.26	650.73
10/28/99	6.80	633.62	7.20	633.66	10.10	630.26	18.60	674.62	45.95	670.85	41.95	674.68	19.70	696.95	NT	NT
09/30/2002	7.10	633.32	7.58	633.28	10.68	629.68	18.83	674.39	44.03	672.77	41.95	674.68	20.63	696.02	34.69	658.3
03/18/2003	6.70	633.72	7.15	633.71	9.20	631.16	19.08	674.14	44.80	672	42.55	674.08	21.15	695.5	34.40	658.59
09/04/2003	7.85	632.57	8.40	632.46	11.80	628.56	20.10	673.12	45.45	671.35	43.35	673.28	21.95	694.7	36.00	656.99
03/03/2004	7.40	633.02	7.90	632.96	10.35	630.01	20.45	672.77	45.80	671	43.85	672.78	21.90	694.75	35.80	657.19
09/04/2004	7.60	632.82	8.20	632.66	11.00	629.36	20.60	672.62	45.95	670.85	43.70	672.93	21.85	694.8	dry	dry
		,														
		٠.														
		·	_									,				:
	_				-		_		_		-		-			
Average	6.69		7.18		9.19		18.53		50.62		43.64		19.42		38.21	
Std. Dev.	0.77	·	0.82		1.61		1.38		7.57		3.67		2.10		3.49	
	11.47%		11.45%		17.52%		7.42%		14.95%		8.41%		10.83%		9.14%	
Maximum	7.85	b	8.40		11.80		20.60		70.75	l I	52.57		21.95		42.30	
Minimum	0.00		6.05		7.08		16.44		44.03		39.38		16.35		0.00	

ATTACHMENT D Groundwater Contour Map





FOX Engineering Associates, Inc. 1601 Golden Aspen Drive, Suite 103 Ames, Iowa 50010 Phone: 515 233-0000 FAX: 515 233-0103 SITE PLAN
GROUNDWATER CONTOUR MAP SEPTEMBER 2004

MUSCATINE C & D LANDFILL MUSCATINE, IOWA

FIGURE: 1								
REVISION	NO.	DATE						
DRAWN JAK	PROJECT NO. 6008-03B	DATE 11-23-04						

ATTACHMENT E Closure Permit & Amendments



STATE OF IOWA

THOMAS J. VILSACK, GOVERNOR SALLY J. PEDERSON, LT. GOVERNOR

DEPARTMENT OF NATURAL RESOURCES

JEFFREY R. VONK, DIRECTOR

October 11, 2004

Lavene Payne, Solid Waste Manager City of Muscatine 1000 S Houser Muscatine, IA 52761

RE. City of Muscatine C & D Landfill (CLOSED) 2003 Annual Water Quality Report Permit No. 70-SDP-04-78C

Dear Mr. Payne:

We have reviewed the 2003 Annual Water Quality Report (AWQR), dated November 20, 2003, as submitted on your behalf by FOX Engineering Associates, Inc.

Based on our review of the report, the Department authorizes continued implementation of the recommended monitoring program, as follows:

1. Continued semiannual water quality analysis shall be conducted at all approved monitoring points as defined in the Special Provisions of the permit and/or any subsequent amendments.

In addition, all future AWQRs should include the following, starting with November 30, 2005 report:

- 1. A brief history of the site that describes the geology, hydrogeology, previous land-use, and solid waste streams.
- 2. An 11"x17" scaled site map delineating the approved monitoring network. All groundwater and surface water monitoring points shall be conspicuously marked and show its function as an upgradient, background, or downgradient sampling location.
- 3. A groundwater table contour map to evaluate groundwater pathways and to evaluate potential groundwater mounding. Data from leachate piezometers or wells should be included on the groundwater table contour map.
- 4. A potentiometric map should be included if a confined unit is being monitored.
- 5. A discussion of potential groundwater mounding and its influence on upgradient and downgradient wells.
- 6. A table showing all current and historic water quality data.

- 7. An evaluation of all upgradient groundwater and surface water points to determine whether they are currently functioning as a valid background/upgradient sampling points based on the groundwater table contour map and water quality data results.
- 8. Control limit calculations for each upgradient or background groundwater sampling point and whether the corresponding downgradient monitoring point falls within the calculated limits.
- 9. Graphical representation of water quality data in readable form. The current control limits and, if applicable, the Maximum Contaminant Levels (MCLs) should be clearly shown on each graph.
- 10. A discussion of the water quality data results stating whether potential leachate migration is occurring beyond the waste boundary at any groundwater monitoring point. If MCLs are exceeded, provide information on potential receptors.
- 11. A discussion, as applicable, of the potential impact of the landfill on surface water quality.
- 12. Conclusions and recommendations for future monitoring.

If you have any questions, you may contact me at (515) 281-8968.

Sincerely,

Jeff Simmons

Environmental Engineer

Energy and Waste Management Bureau

JNS\JNS\J:2003WaterQualityltrMuscatineC&D.doc

MMM

copy: Leslie Wolfe, P.E.

FOX Engineering Associates, Inc. 1601 Golden Aspen Drive, Suite 103 Ames, IA 50010

DNR Field Office #6

Nina Koger, DNR

Jeff Simmons, DNR



KECEIVED JUL 0 7 2003

STATE OF IOWA

OMAS J. VILSACK, GOVERNOR SALLY J. PEDERSON, LT. GOVERNOR

DEPARTMENT OF NATURAL RESOURCES

JEFFREY R, VONK, DIRECTOR

DJL _ Binder

July 2, 2003

Lavene Payne, Solid Waste Manager
City of Muscatine
1000 S Houser
Muscatine, IA 52761

RE: City of Muscatine C & D Landfill (CLOSED)
Permit No. 70-SDP-04-78C
Amendment #3

Dear Mr. Payne:

Enclosed is Amendment #3 to the permit issued on December 29, 1994, for the City of Muscatine C & D Landfill (CLOSED). The amendment and approved plans must be kept with the permit and the approved plans at the sanitary disposal project in accordance with solid waste rule 567 IAC 114.26(2)"c". Please review this amendment with your operators, as they must become familiar with it.

In accordance with the February 20, 2003 request from FOX Engineering Associates, Inc., the enclosed amendment authorizes the permit holder to move the schedule of monitoring events one month earlier by 1) Allowing the semiannual sampling to be conducted in March and September of each year; 2) Allowing the annual sampling to be conducted in September of each year; and 3) Allowing the water level measurements to be conducted in March and September of each year.

Note that the amendment may contain conditions that require a response or action by you, which if not properly complied with, may prompt enforcement action by this department.

If you have any questions, you may contact me at 515/281-8968.

Sincerely,

Jeff Simmons

Environmental Engineer

Energy & Waste Management Bureau

JNS\JNS\J:MuscatineC&D94amd3X.doc

IOWA DEPARTMENT OF NATURAL RESOURCES AMENDMENT #3

Issued by:

Vina M. Koger

Environmental Services Division

For: the Director

Date Issued:

July 2, 2003

Permit number 70-SDP-04-78C, issued on December 29, 1994, for the City of Muscatine C&D Landfill (CLOSED) is hereby amended by the following:

In accordance with the variance approval of September 15, 1998, the permit holder is authorized to reduce the frequency of groundwater level measurements from monthly, as required by current subrule 567 IAC 114.26(4)"b", to semiannually.

Accordingly, in accordance with the February 20, 2003 request from FOX Engineering Associates, Inc., the permit holder is authorized to conduct water quality sampling and water level measurements in March and September rather than April and October.

Replace Special Provision #5b and #5g with the following:

#5b. Quarterly sampling of the approved monitoring points has been completed. Continued semiannual sampling shall take place in March and September of each year for the parameters listed in 567 IAC 114.26(4)"e". Routine annual testing for the parameters listed in 567 IAC 114.26(4)"f" shall be conducted during September of each year.

The elevation of water in each monitoring well shall be measured and recorded on a semiannual basis in March and September.

#5g. An Annual Water Quality Report (AWQR) summarizing the effects the facility is having on groundwater and surface water quality shall be submitted to the Department's Main and local Field offices by November 30 each year. This report shall be prepared in accordance with 567 IAC 114.26(8)"d" by a Professional Engineer licensed in the State of Iowa. The AWQR shall include the results of the semiannual groundwater measurements and the routine semiannual and annual groundwater quality analyses conducted at the approved monitoring points. By means of a variance granted on September 15, 1998, groundwater measurements may be taken on a semiannual basis.

NMK\JNS\J: MuscatineC&D94amd3.doc



STATE OF IOWA

THOMAS J. VILSACK, GOVERNOR SALLY J. PEDERSON, LT. GOVERNOR

DEPARTMENT OF NATURAL RESOURCES
JEFFREY R. VONK, DIRECTOR

January 18, 2002

Robert McDonald, P.E. Assistant City Engineer Department of Public Works 1459 Washington Street Muscatine, IA 52761-5042

SUBJECT: City of Muscatine C&D Landfill

Mad-16

#70-SDP-4-78C

Dear Mr. McDonald:

This letter constitutes Amendment #2 to the permit issued December 29, 1994 for the City of Muscatine C&D Landfill. The amendment and approved plans must be kept with the permit and the approved plans at the sanitary disposal project in accordance with solid waste rule 103.2(2)'c', IAC. Please review this amendment with your operators, as they must become familiar with it.

The amendment adds the following as a Special Provision to your permit:

The Emergency Response and Remedial Action Plan (ERRAP) prepared by Fox Engineering Associates, Inc. that was received on December 28, 2001 is in compliance with 567 IAC 102.16 and is hereby approved. An updated ERRAP shall be submitted at the time of any significant changes in facility closure operations that require modification of the currently approved ERRAP.

If you have any questions regarding this amendment, please contact Nina M. Koger at (515) 281-8986.

Sincerely,

Lavoy Haage Supervisor

Solid Waste Section

LH:nmf

ATTACHMENT

cc: Field Office 6

N. Koger, IDNR

F. Hallada, IDNR

A.J. Johnson, City Administrator City Hall Muscatine, IA 52761

Lavene Payne, Solid Waste Manager Public Works Bldg. 1459 Washington Street Muscatine, IA 52761

Fox Engineering 1601 Golden Aspen Drive, Suite 103 Ames, IA 50010

DEPARTMENT OF NATURAL RESOURCES

LARRY J. WILSON, DIRECTOR

September 15, 1998

Robert McDonald, P.E. Assistant City Engineer Department of Public Works 1459 Washington Street Muscatine, IA 52761-5042

SUBJECT: Muscatine County Sanitary Landfill

#70-SDP-4-78C C+D landfill

Dear Mr. McDonald:

Enclosed is Amendment #1 to the permit issued December 29, 1994 for the Muscatine County Sanitary Landfill. The amendment must be kept with the permit and the approved plans at the sanitary disposal project in accordance with solid waste rule 103.2(2)'c', IAC. Please review this amendment with your operators, as they must become familiar with it.

The enclosed amendment (1) authorizes a reduction in the frequency of water level measurements from a monthly basis to a semiannual basis; (2) authorizes the permit holder to cease methane gas monitoring and annual reporting; and (3) authorizes a reduction in the frequency of routine site inspections from a monthly basis to a semiannual basis.

Please note that the permit contains special provisions that may require a response or action by you which, if not properly complied with, may prompt enforcement action.

If you have any questions regarding this amendment, please contact Nina M. Koger at (515) 281-8986.

Sincerely,

Lavoy Hazge Supervisor

Solid Waste Section

LH:nmf

ATTACHMENT

DEDICEIMET TO, TOO

.cc: Field Office 6

N. Koger, IDNR

F. Hallada, IDNR

A.J. Johnson, City Administrator City Hall Muscatine, IA 52761

Lavene Payne, Solid Waste Manager Public Works Bldg. 1459 Washington Street Muscatine, IA 52761

Fox Engineering 1531 Airport Road Ames, IA 50010 IOWA DEPARTMENT OF NATURAL RESOURCES

AMENDMENT #1

Issued by:

F. Hallada, P.E.

Environmental Protection Division

For: the Director

Date Issued: September 15, 1998

Permit number 70-SDP-4-78C for the Muscatine C&D Sanitary Landfill is hereby amended by the following:

- 1. In accordance with the variance approval of September 15, 1998, the permit holder is authorized to reduce the frequency of groundwater level measurements from monthly, as required by subrule 103.2(4)b IAC, to semiannually. The measurements shall be taken in April and October of each year, with the results submitted in the corresponding semiannual monitoring reports.
- 2. In accordance with the variance approval of September 15, 1998, the permit holder is authorized to cease methane gas monitoring and annual reporting, as required by IAC Subrule 103.2(15). However, in the event that methane gas is found to be present at the site, gas monitoring shall be immediately implemented.
- 3. The permit holder is authorized to reduce the frequency of routine site inspections from monthly, as required by Special Provision #6 of the permit, to semiannually. The inspections shall be conducted in April and October of each year, with the results submitted in the corresponding semiannual engineering inspection reports.



70-302-4-78C St.

TRRY E. BRANSTAD, GOVERNOR

DEPARTMENT OF NATURAL RESOURCES
LARRY J. WILSON, DIRECTOR

December 29, 1994

Lavene Payne, Solid Waste Manager Department of Public Works 1459 Washington Street Muscatine, IA 52761-5042

Re: · City of Muscatine C&D Landfill

#70-SDP-4-78C

Dear Mr. Payne:

Enclosed is the closure permit for the City of Muscatine Construction and Demolition Sanitary Landfill. The permit and the approved plans must be kept on file for post closure use and reference. Please review the closure permit and plans with your staff, as they must become familiar with them.

Please note that the permit contains special provisions that may require a response or action by you which, if not properly complied with, may prompt enforcement action.

The permit is authorized continued use of the area as a construction rubble fill site.

If you have any questions regarding this permit, please contact Nina M. Koger at (515) 281-8986.

Sincerely,

Lavoy Haage Supervisor

Solid Waste Section

LH: nmf

ATTACHMENT

cc: Field Office 6

N. Koger, IDNR

F. Hallada, IDNR

A.J. Johnson, City Administrator City Hall Muscatine, IA 52761

Mr. Robert McDonald, P.E. Public Works Bldg. 1459 Washington Street Muscatine, IA 52761

Jim Mikolaitis, P.E. GES, Inc. P.O. Box 9007 Cedar Rapids, IA 52409-9007

IOWA DEPARTMENT OF NATURAL RESOURCES SANITARY DISPOSAL PROJECT PERMIT

I. Permit Number: 70-SDP-4-78C

II. Permitted Agency: City of Muscatine

III. Project Location: Part of the NE 1/4, Sec. 3, T76N,

R2W, 3 Acres, Muscatine County, Iowa

IV. Responsible Official

Name: Lavene Payne, Solid Waste Manager

Address: Department of Public Works

1459 Washington Street Muscatine, IA 52761-5042

Phone: 319/263-8933

V. Registered Design Engineer

Name: Jim Mikolaitis, P.E.

Address: Howard R. Green Company

P.O. Box 9007

Cedar Rapids, IA 52409-9007

Phone: 319/395-0578

Registration Number: 11949

VI. Date Permit Issued: December 29, 1994

VII. Permit Expiration Date: December 29, 2024

VIII. Issued by:

Environmental Protection Division

for the Director

IX. General Provisions

The above named permitted agency is hereby authorized to close the sanitary landfill at the described location in conformance with Chapter 455B of the Code, the rules pursuant thereto existing the time of issuance, and any subsequent new rules which may be duly adopted, and any provisions contained in Section X of this permit.

The facility shall be closed according to the engineering plans and specifications approved by the Department of Natural Resources and these shall become a part of this permit. Any modifications or deviations from the engineering plans and specifications must have prior approval by the Department and an amendment to this permit issued.

The issuance of this permit in no way relieves the applicant of the responsibility for complying with all other local, state, and federal statutes, ordinances, and rules or other requirements applicable to the closure and maintenance of this closed sanitary landfill.

No legal or financial responsibility arising from the closure and post closure of the approved project shall attach to the state of Iowa or the Department of Natural Resources due to the issuance of this permit.

If title to this project is transferred, the new owner must apply to the Department for a transfer of this permit within thirty days of the date of title transfer. This transfer is void sixty days after the date of title conveyance unless the Department has transferred the permit.

This facility shall be surveyed as necessary and inspected as described in the special provisions of this permit. Semiannual reports shall be prepared containing a brief report describing the site's conformance and nonconformance with the permit and the approved plans and specifications during the inspections. These reports shall be submitted by May 1 and November 1 each year to both the Field and Main offices of the Department. The Department shall be notified if any inspection reveals any nonconformance with the permit and approved plans and specifications.

Failure to comply with Chapter 455B of the Code, or any rule of order promulgated pursuant thereto, or any or all provisions of this permit may result in a civil penalty of up to \$5000 for each day of violation, pursuant to Section 455B.307 of the Code.

X. Special Provisions

- 1. The thirty-year post closure period for this facility begins on the date of issuance of this Closure Permit.
- 2. This site shall be closed and maintained in accordance with the approved Construction and Demolition Debris/Construction Rubble Landfill Closure and Post Closure Plan (C/PCP), dated May 2, 1994, and Plans dated March 19, 1994, as submitted by Green Environmental Services, Inc. (GES).
- 3. Issuance of this closure permit prohibits any additional regulated waste disposal, recycling, composting, and other related landfill activities which are subject to permit approval. However, the permit holder is

authorized continued use of the closed landfill for construction rubble fill, in accordance with the approved documents and permit conditions.

- The permit holder shall submit a closure compliance 4. report certified by a professional engineer registered in the State of Iowa upon completion of the final cap placement. The report shall certify that the site closure has been implemented in compliance with the rules, the Closure and Post Closure Plan, and the permit. following information must be included in the report:
 - As built plans showing changes from approved design a. plans, including the grading and seeding of borrow areas.
 - A copy of the notation filed with the county recorder showing, for the purposes of title abstract, the existence of a landfill on the property, the types of wastes disposed of and dates of landfill use.
- 5. This site shall be monitored for water quality in accordance with the approved Hydrogeologic Investigation Report and Hydrologic Monitoring System Plan (HMSP), dated February 28, 1994, as submitted by GES.
 - The HMSP shall include groundwater monitoring points a. MW-2, MW-3, MW-4, MW-6, and MW-7
 - In addition, monitoring points MW-1, MW-5, and PZ-8 shall be retained as water level measuring points.
 - First year quarterly sampling shall begin in April Subsequent quarterly sampling shall continue in July and October 1995, and January 1996 for analysis of the parameters listed in subrule 103.2(4)d and e IAC. Continued semiannual sampling shall take place in April and October of each year for the parameters listed in subrule 103.2(4)e IAC, beginning in April 1996. Routine annual testing for the parameters listed in subrule 103.2(4)f shall be conducted during October of each year, beginning in October 1995.
 - Samples collected for dissolved metals analysis c. shall be field filtered, preserved, and promptly transferred to a certified laboratory.
 - d. The Method Detection Limit (MDL) for the test parameters shall not exceed action levels as defined under IAC Chapter 133. If the action levels cannot be feasibly achieved using procedures described in

IAC Subrule 103.2(5), then the MDL shall not exceed the lowest feasible level.

- If laboratory test results exceed the upgradient e. mean plus two standard deviations or the Maximum Contaminant Level (MCL) for any parameter, the Department shall be notified within 30 days of receipt of the analytical results.
- f. Results of all analysis and the associated sampling forms shall be submitted to both the field and main offices of this department within 45 days of the sample collection.
- annual report summarizing the effects An facility is having on groundwater and surface water quality shall be submitted to the Department by November 30 of each year. This report shall be prepared in accordance with IAC Subrule 103.2(8)d by a professional engineer registered in the state of Iowa. This report shall include the results of groundwater level measurements conducted in the monitoring wells.
- This site shall be inspected monthly for the first year, or more frequently depending on weather conditions. The frequency of routine inspections may be decreased, after the first year, but no less frequent than semiannually, if the permit holder provides justification that monthly inspections are no longer necessary to ensure proper maintenance of the site. Summarize all inspection data in the semiannual report defined in the General Provisions.
- All diversion and drainage systems must be maintained to the approved specifications to prevent run-on and runoff erosion, or other damage to the final cover. These diversion and drainage structures must be designed to meet a 25-year, 24 hour rainfall event.
- 8. The vegetative cover shall be reseeded as necessary to maintain good vegetative growth. Any invading vegetation whose root system could damage the compacted soil layer shall be removed or destroyed immediately.
- 9. The integrity and effectiveness of the final cover must be maintained by making repairs as necessary to correct the effects of settling, subsidence, erosion, or other events. If damage to the final cover compacted soil layer occurs, repairs shall be made to correct the damage and return it to original specifications.
- The permit holder shall quarterly monitor and annually 10. report site methane concentrations in accordance with subrule 103.2(15) IAC after May 18, 1994.

actions, as defined in the rules, shall be taken in the event of methane gas level limit exceedances. The annual report summarizing the methane gas monitoring results and any action taken resulting from gas levels exceeding the specified limits during the previous 12 months shall be submitted by November 30 of each year.

- 11. The permit holder is conditionally exempt from providing and implementing a leachate control system plan. Continued exemption is subject to compliance with water quality standards, statistical limits per IAC subrule 103.2(6) through 103.2(8), and the control of leachate at the site. In the event that these conditions are violated, the permit holder shall be required to submit a groundwater quality assessment plan in accordance with IAC subrule 103.2(9).
- 12. The permit holder is exempt from Financial Assurance requirements, as provided in IAC Chapter 111, since municipal solid waste has not been disposed of at this facility.